ANTLE RESIDENCE
3119 COLORADO AVE.
ORLANDO, FL 32826

BUILDING DATA

- 2023 FLORIDA BUILDING CODE RESIDENTIAL, 8th EDITION
- FLORIDA ELECTRICAL CODE 2020
- 2023 FBC RESIDENTIAL 8th EDITION - PLUMBING
- 2023 FBC RESIDENTIAL 8th EDITION - ELECTRICAL


IMPERVIOUS AREA CALC.'S

IMPERVIOUS AREA	2,066 SQ. FT.
TOTAL LOT AREA	7,059 SQ. FT.
IMPERVIOUS %	29 %



RENDERING

N.T.S.




SITE MAP

N.T.S.

DRAWING INDEX

C	SITE MAP & SITE PLAN
GN	GENERAL NOTES
01	DEMOLITION PLAN
02	FLOOR PLAN & DIMENSION PLAN
03	ELEVATIONS & RENDERING4
04	BUILDING SECTION
05	ELECTRICAL LAYOUT
S0	STRUCTURAL NOTES
S1	FOUNDATION PLAN
S2	FRAMING PLAN
S3	LINTEL PLAN
SD1	STRUCTURAL DETAILS
SD2	STRUCTURAL DEATILS



SITE PLAN

1/8"=1-0"

NOTE:
SITE PLAN CREATED FROM OWNER PROVIDED SITE PLAN. DRAFTER IS NOT RESPONSIBLE FOR SURVEY ERRORS.

NOTE:
NO MODIFICATION TO LOT GRADING OR IN-FILL REQUIRED

NOTE:
THIS DOES NOT CONSTITUTE AS A SURVEY.
SIGNED:_____
DATE:_____

NOTE:
THE TRUSS PACKAGE WILL BE REVIEWED AND APPROVED BY THE E.O.R. AS PART OF THE SIGNED AND SEALED SUBMITTAL

1	BUILDING DEPARTMENT COMMENTS
2	BUILDING DEPARTMENT COMMENTS
3	BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
COVER SHEET & SITE PLAN

DESIGN	DRAWN CB
CHECKED	
JOB ANTLE ADDITION	
SCALE AS NOTED	
DATE 10.15.2025	

SHT 1 OF 04

C

GENERAL NOTES

DESIGN REQUIREMENTS

DESIGN LIVE LOADS(MINIMUM):
A. FLOORS - 40 PSF
B. BALCONIES - 60 PSF
C. DECKS - 60 PSF
D. ATTIC WITHOUT STORAGE - 10 PSF
E. ATTIC WITH LIMITED STORAGE - 20 PSF
F. GUARDRAILS AND HANDRAILS - 200 PLF
G. GUARDRAILS IN-FILL COMPONENTS - 50 PLF
H. ROOMS OTHER THAN SLEEPING ROOM - 40 PSF
I. SLEEPING ROOM - 30 PSF
J. STAIRS - 40 PSF

WIND DESIGN LOAD INFORMATION-
(PER FBC 2023 8th EDITION R301, REF. ASCE 7-22)
BASIC WIND SPEED (V_{ult}) = 145 MPH (3 SECOND GUST)
(V_{asd}) = 112 MPH (3 SECOND GUST)
BUILDING CATEGORY = II (ASCE 7-22)
WIND EXPOSURE(ALL SIDES) =B (ASCE 7-22)
INTERNAL PRESSURE COEFFICIENTS (ASCE 7-22)
ENCLOSED BUILDINGS = +/-0.18
PARTIALLY ENCLOSED BUILDINGS = +/-0.55
(NOTE: COEFFICIENTS FOR PARTIALLY ENCLOSED STRUCTURES ARE APPLIED WHEN DESIGN OF MEMBER(S) FALLS UNDER ASCE 7-10 DEFINITIONS CLASSIFYING AS SUCH)

ALL COMPONENTS AND CLADDING NOT SPECIFIED ON PLANS SHALL BE DESIGNED TO WITHSTAND THE FOLLOWING PRESSURES (p_{asd}):

FOR WALL LOCATIONS: -30.4 PSF, +22.7 PSF
FOR ROOF LOCATIONS: -53.6 PSF, +13.1 PSF

FOUNDATIONS

1. SOIL TO BE COMPACTED TO AT LEAST 95% UNDER SLABS AND 98% UNDER FOOTINGS OF MAX. DRY DENSITY AS DETERMINED BY ASTM- 1557 (MODIFIED PROCTOR)

2. THE FOUNDATION OF THIS STRUCTURE HAS BEEN DESIGNED TO AN ALLOWABLE BEARING CAPACITY OF 2000 PSF. IT IS THE OWNER/ CONTRACTORS RESPONSIBILITY TO VERIFY THAT THE BUILDING SITE WILL MEET THIS STANDARD WITH REGARDS TO SETTLEMENT AND SUPPORT.

3. PROVIDE TERMITE TREATED SOIL IN ACCORDANCE W/ SECTION R318 OF THE FLORIDA RESIDENTIAL CODE. IN LIEU OF TREATING THE SOIL, BORA-CARE TERMITICIDE MAY BE APPLIED TO WOOD COMPONENTS IN ACCORDANCE TO W/ MANUFACTURER'S INSTRUCTIONS, PURSUANT TO SECTION R318 OF THE FLORIDA RESIDENTIAL CODE.

BOLTS AND THREADED RODS

1. ALL BOLTS & THREADED RODS TO BE ASTM A307 OR BETTER(U.N.O.)

CAST IN PLACE CONCRETE

1. ALL CONCRETE SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS OF 2500 PSI, A SLUMP OF 4" PLUS OR MINUS 1", AND HAVE 2 TO 4% AIR ENTRAINMENT, AND A MAXIMUM WATER/CEMENT RATIO OF 0.58.

2. ALL REINFORCING STEEL SHALL BE NEW DOMESTIC DEFORMED BILLET STEEL CONFORMING TO ASTM A-615 GRADE 60.

3. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A-l85 FOR 6x6xW1.4xW1.4 WWF SHALL BE LAPPED AT LEAST 6" & CONTAIN AT LEAST ONE CROSS WIRE WITHIN THE 6". FIBERMIX OF EQUAL SPECIFICATIONS MAY BE USED IN LIEU OF WWF.

4. ALL CONCRETE WORK SHALL BE IN ACCORDANCE WITH "THE BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE" ACI 318 LATEST EDITION, AND "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS," ACI 301.

5. HORIZONTAL FOOTING BARS SHALL BE BENT MIN. 48 BAR DIAMETERS (EXCLUDING BEND) AROUND CORNERS OR #5 CORNER BARS WITH MIN. 30" LAP EXCLUDING BEND AT EACH END SHALL BE PROVIDED.

6. MINIMUM LAP SPLICES ON ALL REINFORCING BARS SHALL BE 48 BAR DIAMETERS.

WOOD CONSTRUCTION

1. WOOD CONSTRUCTION SHALL CONFORM TO THE NFPA "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION", LATEST EDITION.(NDS)

2. ALL EXTERIOR WOOD STUD WALLS, BEARING WALLS. SHEAR WALLS AND MISC. STRUCTURAL WOOD FRAMING MEMBERS. (I.E. BLOCKING OR GABLE END BRACING), SHALL BE SPRUCE PINE FIR OR EQUIVALENT. NO. 2 GRADE SHALL BE USED REGARDLESS OF SPECIES.

3. ALL 2X8's OR DEEPER TO BE SOUTHERN PINE NO. 2 GRADE

MASONRY WALL CONSTRUCTION

1. HOLLOW LOAD BEARING UNITS SHALL BE NORMAL WEIGHT, GRADE N, TYPE 2, CONFORMING TO ASTM C90, WITH A MINIMUM NET COMPRESSIVE STRENGTH OF 2000 PSI (f'm = 1500 PSI)

2. MORTAR SHALL BE TYPE M OR S, CONFORMING TO ASTM C270

3. HEAD MORTAR JOINTS AT PRECAST WINDOW SILLS TO BE NO MORE THAN 1".

4. COARSE GROUT SHALL CONFORM TO ASTM C476 WITH A MAXIMUM AGGREGATE SIZE OF 3/8" AND A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI.

5. VERTICAL REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS WITH CELLS FILLED WITH COARSE GROUT.

6. VERTICAL REINFORCEMENT SHALL BE HELD IN POSITION AT THE TOP AND BOTTOM AND AT A MAXIMUM SPACING OF 8'-0" U.N.O. REINFORCEMENT SHALL BE PLACED IN THE CENTER OF THE MASONRY CELL TYPICAL UNLESS OTHERWISE NOTED.

7. REINFORCING STEEL SHALL BE LAPPED MINIMUM 25" UNLESS NOTED OTHERWISE ON THE DRAWINGS.

8. HOOKS AT TOP & BOTTOM OF VERTICAL REINFORCING BARS TO BOND BEAM AND FOOTING TO BE NO LESS THAN 12 BAR DIAMETERS EXCLUDING BEND

9. EXPANSION TYPE ANCHORS ARE NOT TO BE USED IN BOND BEAM. EMBEDDED ANCHORS OR EPOXY FASTENED STUDS SHALL BE USED.

PREFABRICATED WOOD TRUSSES

1. ALL PREFABRICATED WOOD TRUSSES SHALL BE SECURELY FASTENED TO THEIR SUPPORTING WALLS OR BEAMS WITH HURRICANE CLIPS OR ANCHORS.

2. TRUSSES SHALL BE DESIGNED BY MWFRS METHODOLOGY FOR LONG SPAN TRUSSES TO DETERMINE UPLIFT AND REACTION VALUES. MEMBER AND PLATE DESIGN TO BE CALCULATED BY COMPONENTS AND CLADDING METHOD UNLESS SPECIFIED OTHERWISE BY TRUSS ENGINEER OF RECORD

3. PREFABRICATED WOOD TRUSSES SHALL BE DESIGNED IN ACCORDANCE WITH THE LATEST EDITION OF THE "NATIONAL DESIGN SPECIFICATION FOR STRESS-GRADE LUMBER AND ITS FASTENERS" AS RECOMMENDED BY THE NATIONAL FOREST PRODUCTS ASSOCIATION.

4. TRUSS MEMBERS AND CONNECTIONS SHALL BE PROPORTIONED (WITH A MAXIMUM ALLOWABLE STRESS INCREASE FOR LOAD DURATION OF 25%) TO WITHSTAND DESIGN LOADS.

5. BRIDGING FOR PRE-ENGINEERED TRUSSES SHALL BE AS REQUIRED BY TRUSS MANUFACTURER UNLESS NOTED ON PLANS

6. TRUSS ELEVATIONS AND SECTIONS ARE FOR GENERAL CONFIGURATION OF TRUSSES ONLY. WEB MEMBERS ARE NOT SHOWN, BUT SHALL BE DESIGNED BY TRUSS MANUFACTURER IN ACCORDANCE WITH THE DESIGN LOADS.

TRUSS DESIGN LOADS :
TOP CHORD : LL = 20 PSF
(TRUSS MNF. MAY TAKE REDUCTION FOR 6:12 SLOPES OR GREATER)
DL = 10 PSF (SHINGLE TYPE ROOF COVER)
DL = 20 PSF (TILE TYPE ROOF COVER)
DL = 14 PSF AT OVERBUILT
BOTTOM CHORD : LL = 10 PSF
BOTTOM CHORD : DL = 10 PSF (15 PSF FOR PLASTER CEILING)
WIND LOAD : SEE DESIGN REQUIREMENTS

7. THE TRUSS MANUFACTURER SHALL DETERMINE ALL SPANS, WORKING POINTS, BEARING POINTS, AND SIMILAR CONDITIONS. TRUSS SHOP DRAWINGS SHALL SHOW ALL TRUSSES, ALL BRACING MEMBERS, AND ALL TRUSS TO TRUSS HANGERS.

8. PROVIDE ADDITIONAL BRACING AND BLOCKING PER BCSI-1-03 AND TRUSS MANUFACTURER'S DRAWINGS

BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN
INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
GENERAL NOTES

DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT 2 OF 04
GN

DEMOLITION NOTES:


1. G.C. TO CONTACT DESIGN PROFESSIONAL IF EXIST. CONDITIONS VARY FROM PLANS.
2. G.C. TO VERIFY WALLS AS NON-LOAD BEARING BEFORE REMOVAL OR PROVIDE SHORING AS REQ'D.
3. ALL CHARRED GYPSUM BOARD TO BE REMOVED AND REPLACED. ADDITIONAL WATER AND SMOKE DAMAGED GYPSUM BOARD TO BE REMOVED AND REPLACED AT G.C.'s DISCRETION OR SEALED APPROPRIATELY TO ELIMINATE ODORS. GYPSUM BOARD TO ALSO BE REMOVED AS REQUIRED TO REPLACE INSULATION AFFECTED BY SMOKE.
4. ALL CHARRED WOOD AND SHEATHING TO BE REMOVED AND REPLACED.
5. ALL WINDOWS, DOORS, CABINETRY, COUNTERS, APPLIANCES, FIXTURES AND SHELVING TO BE REMOVED AND REPLACED AT G.C.'S DISCRETION OR SEALED/CLEANED APPROPRIATELY TO ELIMINATE ODORS/STAINS.

LEGEND

EXISTING TO REMAIN

EXISTING TO BE REMOVED

G.C. TO SHORE ALL ROOF FRAMING BEFORE REMOVAL OF LOAD BEARING WALL.



DEMOLITION PLAN

1/8"=1'-0"

KEY PLAN

1/16"=1'-0"

BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
DEMOLITION PLAN

DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT 1 OF 04

01

LEGEND

HATCH INDICATES NEW 2x4 (U.N.O.) FRAMING (LOAD BRG.) STUDS @16" O.C. (PROVIDE MID-SPAN BLOCKING AT ALL INT. BRG.)

HATCH INDICATES NEW CMU WALL T.O.W. @10'-0" A.F.F.

INDICATES GROUT FILLED CELL WITH (1) VERT. #5 CONT. FTG. TO BOND BEAM (8'-0" O.C. MAX U.N.O.)(REFER TO NOTES ON COVER SHEET)

DOOR/WINDOW SCHEDULE


NOTE: VERIFY ROUGH OPENINGS WITH WINDOW/DOOR MANUFACTURER BEFORE FRAMING

A	1	42 X 96" ENTRY DOOR
B	1	47 in. x 62 in. PGT PW4053 VINYL PICTURE WINDOW
C	1	PGT SH5400 2753 VINYL SINGLE HUNG WINDOW (EERO) ⚠1
D	2	36" x 80" INTERIOR DOOR


SQ.FT. CALC'S

EXISTING LIVING SPACE	1,752 SQ. FT.
PROPSED ADDITION	314 SQ. FT.
TOTAL LIVING SPACE	2,067 SQ. FT.


NOTE:
G.C TO FIELD VERIFY WINDOW/ DOOR SIZES PRIOR TO WINDOW/ DOOR PURCHASE.



PROPOSED FLOOR PLAN
3/8"=1'-0"



DIMENSION PLAN
3/8"=1'-0"



KEY PLAN
1/16"=1'-0"

BUILDING DEPARTMENT COMMENTS
1 BUILDING DEPARTMENT COMMENTS
2 BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN


PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
PROPOSED FLOOR PLAN

DESIGN	DRAWN CB
CHECKED	
JOB ANTLE ADDITION	
SCALE AS NOTED	
DATE 10.15.2025	


SHT 2 OF 04

02




REAR ELEVATION

1/4"=1'-0"




RIGHT ELEVATION

1/4"=1'-0"



BUILDING SECTION '1'

1/4"=1'-0"



BUILDING SECTION '2'

1/4"=1'-0"

BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
EXTERIOR ELEVATIONS

DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT 3 OF 04

03

ELECTRICAL NOTES:


1. THIS ELECTRICAL PLAN IS TO BE USED FOR PLACEMENT PURPOSES ONLY. DESIGN AND CALCULATIONS TO BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR.
2. LOCATION OF EXISTING UNDERGROUND UTILITY LINES AND STRUCTURES SHALL BE DETERMINED AND VERIFIED IN THE FIELD PRIOR TO COMMENCING WORK, ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR HIS DAMAGE TO OTHER TRADES.
3. ELECTRICAL BOXES INSTALLED IN FLOORS, WALLS, OR CEILINGS SHALL BE MOUNTED FLUSH WITH FINISHED SURFACE AND CONDUITS AND/OR CABLES SHALL BE CONCEALED UNLESS OTHERWISE NOTED.
4. EXTERIOR, GARAGE, KITCHEN, BATHROOM OR ANY OUTLETS WITHIN 6' OF A WATER SOURCE ARE GFI.
5. ALL SMOKE DETECTORS TO BE INSTALLED PER NEC 2008.
6. ALL 15-20 AMP BRANCH CIRCUITS THAT SUPPLY OUTLETS IN FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS OR AREAS PER NEC 210.12(B) SHALL BE PROTECTED BY AN ARC-FAULT INTERRUPTER(S) OR COMBINATION TYPE.
7. ALL ELECTRICAL WORK AND APPLIANCES SHALL CONFORM TO NEC 2008.
8. EXCEPTIONS FROM GFI REQUIREMENTS SHALL BE PERMITTED PROVIDED LOCATION WHERE EXCEPTION IS DESIRED IS ALLOWED PER NEC 2008.
9. CARBON MONOXIDE ALARMS AS SHOWN PER PLAN. ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM THE BUILDING WIRING, BE INTERCONNECTED AND HAVE BATTERY BACKUP. A SINGLE COMBO DETECTOR MAY BE USED ILO INDIVIDUAL SMOKE & CARBON MONOXIDE DETECTORS.
10. ALL 120 VOLT 15-20 AMP RECEPTACLE OUTLETS IN FAMILY ROOMS, DINING ROOMS, LIVING ROOMS, PARLORS, LIBRARIES, DENS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS, OR SIMILAR ROOMS OR AREAS PER NEC 210.12(B) SHALL BE TAMPER RESISTANT TYPE PER NEC SECTION 406.11.
11. VERIFY LOCATION OF ALL COMPONENTS w/ HOMEOWNER PRIOR TO COMMENCEMENT OF WORK
12. ALL OUTLETS TO BE TAMPER RESISTANT
13. ALL WIRING IS TO BE #12 AWG OR LARGER SOLID COPPER TYPE THHN AND ELECTRICAL SERVICE WIRING IS TO BE TYPE THW OR THWN.
14. ALL WIRING IS TO BE SHEATHED NM OR NMC WHERE REQ'D (ROMEX)
15. USE CLAMPING TYPE ROMEX CONNECTORS AT EACH BOX.
16. EACH CIRCUIT IS TO HAVE CONTINUOUS SOLID COPPER BARE GROUND WIRE CONNECTED TO EQUIPMENT GROUND BAR IN THE MAIN DISTRIBUTION PANEL. ALTERNATE INSTALLATION OF A GREEN PIGTAIL FROM THE GROUND SCREW TO THE LUG ONTHE BOX WHERE THE GREEN GROUND WIRE IS CONNECTED. (if metal box)
17. LOW VOLTAGE COMPONENTS BY OTHERS
18. PROVIDE NEW CONDUIT FOR NEW WIRING TO MATCH EXISTING
19. ALL OUTLET AND FIXTURE BOXES IN FIRE PARTITIONS TO BE MIN. 1 HR RATED (U.L. LISTED) AND INSTALLED PER MANUF. SPECS.
20. PROVIDE PHOTO SENSOR OR TIMER FOR EXT. LIGHTS.

LEGEND

- EXISTING CMU WALL TO REMAIN
- HATCH INDICATES NEW CMU WALL T.O.W. @10'-0" A.F.F.
- ■ INDICATES GROUT FILLED CELL WITH (1) VERT. #5 CONT. FTG. TO BOND BEAM (8'-0" O.C. MAX U.N.O.)(REFER TO NOTES ON COVER SHEET)


ELECTRICAL LEGEND

- $ SWITCH, SINGLE POLE
- $3 SWITCH, THREE WAY
- $4 SWITCH, FOUR WAY
- $D SWITCH, SINGLE POLE 120V DIMMER
- $3D SWITCH ,THREE WAY 120V DIMMER
- OUTLET 110-115
- G.F.I. OUTLET 110-115, GROUND FAULT CIRCUIT INTERRUPTER
- WP G.F.I. OUTLET 110-115, WATER PROOF G.F.I.
- OUTLET 110-115, SPLIT WIRED
- OUTLET 110-115, CEILING MOUNTED
- OUTLET 110-115, FLOOR MOUNTED
- OUTLET 220-240, SPECIAL PURPOSE
- OUTLET 110-115, QUAD
- LIGHT FIXTURE, CEILING MOUNTED
- LIGHT FIXTURE, WALL MOUNTED
- LIGHT FIXTURE, HANGING
- LIGHT FIXTURE, RECESSED
- VP LIGHT FIXTURE, RECESSED VAPOR PROOF
- LIGHT FIXTURE, TRACK
- E LIGHT FIXTURE, RECESSED EYEBALL, ADJUSTABLE
- PC LIGHT FIXTURE, LAMP HOLDER W/ PULL CHAIN
- LIGHT FIXTURE, FLUORESCENT FIXTURE
- LIGHT FIXTURE, FLOOD LIGHTS
- TELEVISION OUTLET
- TELEPHONE OUTLET
- INTERCOM
- CHIMES
- SD SMOKE DETECTOR
- CM CARBON MONOXIDE DETECTOR
- EXHAUST FAN
- GARBAGE DISPOSAL
- DC DISCONNECT SWITCH
- ELECTRICAL PANEL
- F CEILING FAN, INSTALLED
- P CEILING FAN, PREWIRED
- J JUNCTION BOX
- T DIGITAL THERMOSTAT
- METER



PROPOSED ELEC. LAYOUT PLAN

3/8"=1'-0"



KEY PLAN

N.T.S.

1	BUILDING DEPARTMENT COMMENTS
2	BUILDING DEPARTMENT COMMENTS
3	BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

1NCEPTION DRAFTING &DESIGN

NCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
PROPOSED ELECTRICAL LAYOUT PLAN

DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025


SHT 4 OF 04

04

FOUNDATION NOTES:

1. PROVIDE MIN. 6 MIL. APPROVED VAPOR BARRIER. ALL JOINTS TO BE LAPPED MIN. 6" AND SEALED.
2. PROVIDE 3-1/2" CONC. SLAB W/ 6x6xW1.4xW1.4 WELDED WIRE MESH PLACED AT MID DEPTH ON 6 MIL. VAPOR BARRIER ON 4" MIN. TERMITE TREATED COMPACTED FILL (FIBER MESH MAY BE USED ILO WWM, WHEN FIBER MESH. MEETS OR EXCEEDS SPECIFICATIONS SET FORTH IN THE 2023 FLORIDA BUILDING CODE RESIDENTIAL, 8th EDITION.
3. VERT. #5 BAR TO BE HOOKED AT TOP & BOTTOM (FTG. & BOND BEAM ENDS) W/MIN. 12 BAR DIAMETER LEGS EXCLUDING BEND @ EA. END. LAP SPLICES SHALL BE NO LESS THAN 25".
4. CONSULT W/MAN. SPECIFICATIONS PRIOR TO POURING OR RECESSING DOOR SILLS.
5. EXTERIOR SLABS SHALL SLOPE 1/4" PER FOOT AWAY FROM HOUSE.
6. CONTROL JOINTS (IF SHOWN) ARE NOT REQUIRED BY CODE BUT ARE SUGGESTED (ESPECIALLY WHEN USING FIBER REINF. CONC.) CONTROL JOINTS TO BE SAW CUT A DEPTH OF 1/4 OF THE THICKNESS OF THE SLAB. FILL CUT W/APPROVED JOINT MATERIAL OR USE ALTERNATE APPROVED METHOD.

■ INDICATES GROUT FILLED CELL WITH (1) VERT. #5 CONT. FTG. TO BOND BEAM (8'-0" O.C. MAX U.N.O.)(REFER TO NOTES)



FOUNDATION PLAN

1/2"=1'-0"

BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN
INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
FOUNDATION PLAN

DESIGN	DRAWN CB
CHECKED	
JOB	ANTLE ADDITION
SCALE	AS NOTED
DATE	10.15.2025

SHT6 OF 04

S 1

FRAMING NOTES:

1. THE ROOF PLAN DEPICTED IS NOT INTENDED TO SERVE AS A TRUSS DESIGN.
2. BOND BEAM HEIGHTS VARY. SEE BUILDING SECTIONS, WALL SECTIONS AND ELEVATIONS FOR BEARING HEIGHTS.
3. RAFTER SPACING SHALL BE 24" O.C. MAX. LOCATED @ PRE-ENGINEERED TRUSS LOCATIONS ON OPPOSITE SIDE OF RIDE BEAM.
4. ALIGN TRUSSES AND HAND FRAMING SO ALL GYPSUM WALL BOARD WILL BE CONTINUOUS FROM FLOOR TO CEILING.
5. STRUCTURAL ENGINEER TO INSURE DESIGN CONSIDERATION TO THE FOLLOWING ADDITIONAL LOADS:
   A) ALL CEILING HUNG SOFFITS.
6. REFER TO MANUFACTURER SPECIFICATIONS FOR INSTALLATION REQUIREMENTS OF ALL HARDWARE BEFORE INSTALLATION.
7. PROVIDE BRACING AND BLOCKING PER BCSI-1-03 IN ADDITION TO BRACING AND BLOCKING SHOWN ON PLANS.

NAILING SCHEDULE:

ROOFS:
ROOF SHEATHING TO BE 7/16" O.S.B. OR 15/32" (MIN.) PLYWOOD. REFER TO DETAIL 1 SHEET SD2 FOR NAILING PATTERN SHEATHING TO BE PLACED WITH LONG DIMENSION PERPENDICULAR TO SUPPORTS (TRUSSES). PROVIDE PLY CLIPS @24" O.C. MAX. AT ALL UNSUPPORTED ROOF SHEATHING JOINTS. 2x4 BLOCKING, w/ (2) 10d NAILS EA. END, SHALL BE USED @ALL UNSUPPORTED HIP AND RIDGE AREAS.

NAILS:
NAILS USED IN ALL SHEATHING APPLICATIONS SHALL BE MIN. 8dx2" RING-SHANK (0.113 SHANK DIA.) GUN DRIVEN NAILS. GUN DRIVEN NAILS SHALL HAVE HEAD SIZE 0.28" MIN.

** NAILS FASTENED IN PT. OR FIRE-RETARDANT-TREATED WOOD SHALL BE HOT DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE OR COPPER.

SIMPSON HARDWARE NOTES:

1. SEE "INSTRUCTIONS TO THE INSTALLER" IN SIMPSON STRONG-TIE WOOD CONSTRUCTION CONNECTOR'S CURRENT MANUAL & READ ALL PAGES OF GENERAL NOTES.
2. FILL ALL HOLES IN STRAPS (U.N.O.) TYPICAL TO OBTAIN MAXIMUM UPLIFT.
3. FOR MISLOCATED EMBEDDED ANCHOR GREATER THAN 1/8" BUT LESS THAN 1-1/2" FROM FACE OF TRUSS / RAFTER, INSTALL WOOD SHIMS AND USE 10dX3" NAILS IN LIEU OF 10dx1-1/2" NAILS (MATCH QTY. OF FASTENERS) OR PROVIDE NEW ANCHOR PER NOTE 4.
4. FOR MISLOCATED EMBEDDED ANCHOR MORE THAN 1-1/2" FROM FACE OF TRUSS/ RAFTER, SIMPSON MTSM16 MAY BE FASTENED TO BOND BEAM W/ (4)1/4"x2-1/4" TAPCONS AND (7)10dx1-1/2" NAILS TO TRUSS. THIS IS GOOD FOR UP TO 875 LBS. OF UPLIFT. (2)MTSM16s CAN BE USED FOR UPLIFT TO MAX. 1,750 LBS.

CONNECTOR LEGEND

TYPICAL TRUSS CONN.:

- ALL TRUSS TO MASONRY CONN. TO BE SIMPSON META16 (U.N.O.)
- ALL TRUSS TO TRUSS CONN. DESIGN BY TRUSS MANUF.

1	META16 TRUSS TO BOND BEAM
2	H10A RAFTER TO LOAD BRG. FRAME WALL & EA. RAFTER TO TOP CHORD OF TRUSSES PER DETAIL 7/SD1
3	LSTA18 HEADER TO JACK STUDS
4	H10A TRUSS TO NEW OR EXIST. LOAD BRG. FRAME WALL BELOW
5	SIMPSON RR-R RAFTER TO RIDGE BEAM
6	H1 RAFTER TO LEDGER
7	SIMPSON THA218 TRUSS HANGER TO BOND BEAM
8	SIMPSON LRUZ ZMAX TAILS TO CONT. LEDGER

ROOF VENT CALCULATION

FORMULA
1 SQUARE INCH VENT FOR EVERY 300 SQUARE INCHES OF CEILING
*144 SQ. IN. = 1 SQ. FT.
BLDG. CEILING (SF) X 144 = BLDG. (SQ. IN.)
BLDG (SQ.IN.) / 300 = SQ. IN. OF VENT REQUIRED SQ. IN. OF VENT REQUIRED / 2 = 50% AT RIDGE & 50% AT EAVES.

CALCULATION: FIRST FLOOR

ROOF AREA = 476 SQ. FT.
476 SQ. FT. x 144 = 68,544 SQ. IN.
68,544/ 300 = 228.48 SQ. IN. OF VENT REQUIRED
228.48 SQ. IN. / 2 = 114.24 SQ. IN.
114.24 SQ. IN. (0.8 SQ FT.) OF VENT AT RIDGE AND
114.24 SQ. IN. (0.8 SQ. FT.) OF VENT AT EAVES REQUIRED


REQUIRED VENTILATION

IF OFF-RIDGE VENTS ARE CHOSEN, PROVIDE (2) 4'-0" VENTS OR AS REQUIRED BY MANUF. SPECS.

IF CONTINUOUS RIDGE VENTS ARE CHOSEN, G.C. TO CALCULATE LINEAR FEET NEEDED BASED ON MANUF. SPECS.

NOTE:

1. VENTILATION TO MEET OR EXCEED REQUIREMENTS IN FBCR 2023, 8th EDITION.
2. ROOF VENTS SHOWN ON PLAN REPRESENT AN ESTIMATE OF THE NUMBER REQUIRED VENTS NEED. OFF-RIDGE VENTS ARE BASED ON AN AVERAGE NET FREE AREA OF A TYPICAL VENT (104 SQ. IN.)
3. ACTUAL QUANTITY MAY VARY DEPENDING ON THE ACTUAL NET FREE AREA PROVIDED BY THE CONTRACTOR-SELECTED ROOF VENT MODEL. THE AGGREGATE FREE AREA OF ALL THE ROOF VENTS COMBINED, MUST MEET THE ABOVE MINIMUM CRITERIA AS CALCULATED.
4. VENTS SHOWN ON PLANS ARE TO INDICATE POSSIBLE LOCATIONS AND DO NOT REPRESENT ANY ATTEMPT TO DICTATE LOCATIONS OR CALCULATIONS.



LEGEND

HATCH INDICATES NEW 2x4 (U.N.O.) FRAMING (LOAD BRG.) STUDS @16" O.C. (PROVIDE MID-SPAN BLOCKING AT ALL INT. BRG.)

HATCH INDICATES NEW CMU WALL T.O.W. @10'-0" A.F.F.

INDICATES GROUT FILLED CELL WITH (1) VERT. #5 CONT. FTG. TO BOND BEAM (8'-0" O.C. MAX U.N.O.)(REFER TO NOTES ON COVER SHEET)

ROOF FRAMING PLAN

1/2"=1'-0"

NOTE:
MEMBER SIZES & CONNECTORS TO BE VERIFIED BY STRUCTURAL ENGINEER

NOTE:
THE TRUSS PACKAGE WILL BE REVIEWED AND APPROVED BY THE DESIGN PROFESSIONAL OF RECORD PRIOR TO SUBMISSION

NOTE:
NAILS, BOLTS, SCREWS AND CONNECTORS FASTENED IN PT. OR FIRE-RETARDANT-TREATED WOOD SHALL BE HOT DIPPED ZINC-COATED GALVANIZED STEEL, STAINLESS STEEL, SILICON BRONZE OR COPPER.

BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS
BUILDING DEPARTMENT COMMENTS

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
ROOF FRAMING PLAN

DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT7 OF 04

S2

PRECAST NOTES:

1. PROVIDE FULL MORTAR HEAD AND BED JOINTS.
2. SHORE FILLED LINTELS AS REQUIRED.
3. INSTALLATION OF LINTEL MUST COMPLY WITH THE ARCHITECTURAL AND/OR STRUCTURAL DRAWINGS.
4. LINTELS ARE MANUFACTURED WITH 5-1/2" LONG NOTCHES AT THE ENDS TO ACCOMMODATE VERTICAL CELL REINFORCING AND GROUTING.
5. ALL LINTELS MEET OR EXCEED L/360 VERTICAL DEFLECTION, EXCEPT LINTELS 17'-4" AND LONGER WITH A NOMINAL HEIGHT OF 8" MEET OR EXCEED L/180.
6. BOTTOM FIELD ADDED REBAR TO BE LOCATED AT THE BOTTOM OF THE LINTEL CAVITY.
7. 7/32" DIAMETER WIRE STIRRUPS ARE WELDED TO THE BOTTOM STEEL FOR MECHANICAL ANCHORAGE.
8. CAST-IN-PLACE CONCRETE MAY BE PROVIDED IN COMPOSITE LINTEL IN LIEU OF CONCRETE MASONRY UNITS.
9. SAFE LOAD RATINGS BASED ON RATIONAL DESIGN ANALYSIS PER ACI 318 AND ACI 530
10. BLOCK MASON TO VERIFY LINTEL DEPTHS W/ R.O. PRIOR TO INSTALLATION. CONTACT E.O.R. IF DISCREPANCY EXIST.

SAFE LOAD TABLE NOTES:


1. ALL VALUES BASED ON MINIMUM 4" BEARING. EXCEPTION: SAFE LOADS FOR UNFILLED LINTELS MUST BE REDUCED BY 20% IF BEARING LENGTH IS LESS THAN 6-1/2". SAFE LOADS FOR ALL RECESSED LINTELS BASED ON 8" NOMINAL BEARING.
2. N.R. = NOT RATED.
3. SAFE LOADS ARE TOTAL SUPERIMPOSED ALLOWABLE LOAD ON THE SECTION SPECIFIED.
4. SAFE LOADS BASED ON GRADE 40 OR GRADE 60 FIELD REBAR.
5. ADDITIONAL LATERAL LOAD CAPACITY CAN BE OBTAINED BY THE DESIGNER BY PROVIDING ADDITIONAL REINFORCED MASONRY ABOVE THE PRECAST LINTEL.
6. ONE #7 REBAR MAY BE SUBSTITUTED FOR TWO #5 REBARS IN 8" LINTELS ONLY.
7. THE DESIGNER MAY EVALUATE CONCENTRATED LOADS FROM THE SAFE LOAD TABLES BY CALCULATING THE MAXIMUM RESISTING MOMENT AND SHEAR AT D-AWAY FROM THE FACE OF SUPPORT.
8. FOR COMPOSITE LINTEL HEIGHTS NOT SHOWN, USE SAFE LOAD FROM NEXT LOWER HEIGHT.
9. ALL SAFE LOADS IN UNITS OF POUNDS PER LINEAR FOOT.

TYPE DESIGNATION

F = FILLED WITH GROUT
U = UNFILLED

LXFX-XB

LINTEL MARK
NOMINAL HEIGHT
OF BARS @ BOT.




PRECAST LINTEL LOAD TABLE(COMPOSITE W/(1)#5 TOP & BOTTOM GROUT FILLED SOLID)

LOADS LISTED BELOW HAVE BEEN CALCULATED OR COMPILED FROM DATA FROM THE FOLLOWING APPROVED MAN. CAST-CRETE, QUALITY PRECAST CO., WEKIWA CONCRETE, LOTT'S CONCRETE, AND FLORIDA ROCK IND.

MARK	MAX. CLR. OPENING	6" DEEP	14" DEEP	22" DEEP	38" DEEP	8" DEEP	16" DEEP	24" DEEP	32" DEEP
L1	1'-6"	3984	3665	X	X	3166	6039	9004	10000
L2	2'-4"	2745	3665	X	X	3166	6039	9004	10000
L3	3'-4"	1384	3665	X	2000	1974	4616	7269	9924
L4	4'-6"	1025	3960	2000	X	1060	2483	3913	5350
L5	5'-4"	X	X	X	X	1261	2653	4049	4849
L6	6'-4"	524	N/A	X	X	1055	2542	4029	5047
L8	8'-4"	340	N/A	X	X	635	1534	2436	3127
L9	9'-0"	293	N/A	X	X	483	1170	1857	2404
L10	10'-0"	212	N/A	X	X	483	1170	1857	2555
L11	11'-0"	171	N/A	X	X	488	1224	1966	2721
L12	12'-0"	128	N/A	X	X	419	1053	1692	2341
L13	12'-8"	N/A	N/A	X	X	419	1053	1692	2341
L14	13'-4"	N/A	N/A	X	X	334	842	1352	1879
L16	16'-0"	N/A	N/A	X	X	272	611	988	1380
L18	18'-0"	N/A	N/A	X	X	240	611	1400	1980
L20	20'-0"	N/A	N/A	X	X	183	610	1300	1831
L21	20'-8"	N/A	N/A	X	X	183	610	1300	1831
L22	22'-8"	N/A	N/A	X	X	130	470	1250	1831

1) FOR HEADER DEPTHS DEEPER THAN 32", USE VALUES FOR 32" DEEP HEADER
2) FOR HEADER DEPTHS NOT LISTED ON CHART, USE THE VALUES FOR THE NEXT DEPTH DOWN.
(ex. L3F12 = L3F8)



LINTEL PLAN

1/2"=1'-0"

BUILDING DEPARTMENT COMMENTS
1 BUILDING DEPARTMENT COMMENTS
2 BUILDING DEPARTMENT COMMENTS
3 BUILDING DEPARTMENT COMMENTS

CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN


PROJECT
ANTLE RESIDENCE
ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
LINTEL PLAN


DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT8 OF 04

S3




1 MONOLITHIC FOOTING w/ CMU BLOCK 3/4"=1'-0"




2 WALL SECTION W/ CMU/ MONOLITHIC 3/4"=1'-0"


NOTE:
THE TRUSS PACKAGE WILL BE REVIEWED AND APPROVED BY THE DESIGN PROFESSIONAL OF RECORD PRIOR TO SUBMISSION




3 WEEP SCREED DETAIL N.T.S.




4 MONOLITHIC W/ CMU BLOCK 3/4"=1'-0"




5 MONOLITHIC W/ CMU BLOCK 3/4"=1'-0"




6 EXTERIOR DOOR SILL DETAIL N.T.S.




7 PATIO SLAB CONNECTION DETAIL 3/8"=1'-0"




8 TYPICAL JOINT DETAIL @ CMU WALL 3/8"=1'-0"




9 TYP. CORNER WALL REINFORCING 3/8"=1'-0"




10 BOND BEAM DETAIL 3/4"=1'-0"




11 WINDOW/ DOOR BUCK NOTES N.T.S.




12 CMU OPENING 3/4"=1'-0"




13 TYP. CMU WALL FINISH 3"=1'-0"




14 WINDOW HEAD/JAMB-CMU 3/4"=1'-0"



15 WINDOW SILL-CMU 3"=1'-0"



16 WEEP SCREED DETAIL N.T.S.



17 EXT. WALL SECTION @ ENTRY 1/2"=1'-0"

BUILDING DEPARTMENT COMMENTS	
BUILDING DEPARTMENT COMMENTS	
BUILDING DEPARTMENT COMMENTS	

ÔK CONSTRUCTION

1NCEPTION DRAFTING &DESIGN

NCEPTION DESIGN


PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
DETAILS


DESIGN
DRAWN CB
CHECKED
JOB ANTLE ADDITION
SCALE AS NOTED
DATE 10.15.2025

SHT9 OF 04

SD1



GABLE ROOF




HIP ROOF

ROOF NAILING PATTERN		
ZONE:	1	8d RING-SHANK @6" O.C. EDGES & 12" O.C. FIELD
ZONE:	2	8d RING-SHANK @6" O.C. EDGES & 12" O.C. FIELD
ZONE:	3	8d RING-SHANK @6" O.C. EDGES & 6" O.C. FIELD

NOTE: ALL ROOF SHEATHING JOINTS TO BE STAGGERED


1 ROOF NAILING SCHEDULE

N.T.S.




2 TYP. OVERBUILT VALLEY FRAMING DETAIL

N.T.S.




3 THICKENED EDGE DETAIL

3/4"=1'-0"



4 OUTLOOKER DETAIL

1/2"=1'-0"



5 OVERBUILT FRAMING DETAIL

3/4"=1'-0"

BUILDING DEPARTMENT COMMENTS	
BUILDING DEPARTMENT COMMENTS	
BUILDING DEPARTMENT COMMENTS	
3	
2	
1	

ÔK CONSTRUCTION

INCEPTION DRAFTING &DESIGN

INCEPTION DESIGN

PROJECT
ANTLE RESIDENCE ADDITION
3119 COLORADO AVE
ORLANDO, FL 32826

SHEET TITLE
DETAILS

DESIGN	DRAWN CB
CHECKED	
JOB ANTLE ADDITION	
SCALE AS NOTED	
DATE 10.15.2025	

SHT17OF 04

SD2